


MATCHLINE - SEE SHEET IR-2



LATERAL LINE PIPE SIZING CHART

ALL LATERAL LINES FOR TREE BUBBLERS ON SITE AND ON STREETS SHALL HAVE A MINIMUM SIZE OF 1 INCH.

ALL LATERAL LINES FOR SPRAY HEADS AND BUBBLERS IN PLANTED AREAS SHALL HAVE A MINIMUM SIZE OF 3/4 INCH.

FLOW RANGE	MINIMUM SIZE OF LATERAL LINE
0 THROUGH 5 GPM	MINIMUM SIZE SHALL BE 3/4 INCH
6 THROUGH 11 GPM	MINIMUM SIZE SHALL BE 1 INCH
12 THROUGH 21 GPM	MINIMUM SIZE SHALL BE 1 1/4 INCH
22 THROUGH 30 GPM	MINIMUM SIZE SHALL BE 1 1/2 INCH
31 THROUGH 50 GPM	MINIMUM SIZE SHALL BE 2 INCH

ALL LATERAL LINES SHALL BE SCHEDULE 40 PVC. ALL LATERAL LINES INSTALLED UNDER PAVING SHALL BE PRESSURE TESTED PRIOR TO BURIAL.

POINT OF CONNECTION#1 REFER TO NOTE 'A' BELOW RIGHT

THESE VALVES ARE PLACED HERE ONLY FOR CLARITY, IN REALITY THESE VALVES ARE IN ADJACENT TURF PLANTER

THESE VALVES ARE PLACED HERE ONLY FOR CLARITY, IN REALITY THESE VALVES ARE IN ADJACENT TURF PLANTER

NOTE A:
POINT OF CONNECTION 1 SHALL BE A 6" DOMESTIC (FUTURE RECLAIMED) WATER METER WITH A 8" SERVICE LINE. VERIFY THE ACTUAL LOCATION, SIZE AND WATER PRESSURE IN THE FIELD PRIOR TO STARTING WORK. IF ANY OF THE POC INFORMATION SHOWN ON THESE DRAWING IS FOUND TO BE DIFFERENT THAN THE ACTUAL POC INFORMATION GATHERED IN THE FIELD, IMMEDIATELY NOTIFY THE LANDSCAPE ARCHITECT AND IRRIGATION CONSULTANT. SHOULD THE CONTRACTOR FAIL TO VERIFY THE POC INFORMATION ANY CHANGES REQUIRED BY LOW PRESSURE OR VOLUME SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.



STATIC WATER PRESSURE	162 PSI
DESIGN WATER PRESSURE	107 PSI
MAXIMUM SYSTEM DEMAND	560 GPM
SET PRESSURE REGULATOR @	117 PSI

NOTE:
MAINLINE SHOWN WITHIN PAVING FOR CLARITY ONLY. ACTUAL MAINLINE LOCATION TO BE A MINIMUM OF 18" OFF ADJACENT HARDSCAPE AND OTHER OBSTACLES TYP.

NOTE:
CONTRACTOR SHALL ADJUST ALL HEADS AS REQUIRED TO ACCOMMODATE ANY VERTICAL OBSTRUCTIONS THAT MAY OCCUR, INCLUDING BUT NOT LIMITED TO LIGHT POLES, FIRE HYDRANTS, ETC. VERIFY ALL HEAD LAYOUT WITH OWNER'S AUTHORIZED REPRESENTATIVE PRIOR TO COMMENCING WORK.

NOTE:
BUBBLERS AND LATERAL LINES ARE SHOWN WITHIN PAVING FOR CLARITY ONLY. ACTUAL LOCATION TO BE WITHIN PLANTER. BUBBLERS SHALL BE ALIGNED WITH TREES AND AS DIRECTED BY OWNER'S AUTHORIZED REPRESENTATIVE. CONFIRM ALL LAYOUT IN FIELD WITH OWNER'S AUTHORIZED REPRESENTATIVE PRIOR TO COMMENCING WORK.

KEY MAP




sweeney + associates
IRRIGATION DESIGN AND CONSULTING
California
338750 Sky Canyon Drive, Suite C
Murieta, CA 92563
951-461-6830 p | 951-461-6850 f
email@sweeneyassoc.com
www.sweeneyassoc.com
Murieta, California - Austin, Texas - Ft. Lauderdale, Florida



APPROVED BY:
AL KING, DIRECTOR OF BEACHES, PARKS, & RECREATION DATE:

REVISIONS			
NO.	DESCRIPTION	REVISED	APPROVED

JOB NO.: 100467
SMP NO.: 649-560
SCALE: AS SHOWN
DESIGNED BY: SMP



PLANS PREPARED BY:
SMP
PREPARED UNDER THE SUPERVISION OF:
PATRICK MURPHY
DATE: R.L.A. # 1881

CITY OF SAN CLEMENTE
DEPARTMENT OF BEACHES, PARKS, & RECREATION
LA PATA PARK
IRRIGATION PLAN
(PARKING AND FOOTBALL)

DRAWING NO.: IR-1
SHEET NO.: 63
OF 178

BID SET